

Laboratory Report

Date

15-November-2011

Customer KOMMERLING

Kreditorenbuchhaltung Mulheimerstr,26 D53840 **Troisdorf Germany**

Test No:

AZT0173.11.xls



NATA Accredited Laboratory No: 15147

Azuma Design Pty Limited 160 Newton Rd Wetherill Park. NSW 2164 Ph 02 9604 0255 E-Mail info@azumadesign.com.au

This document is issued in accordance with NATA's accreditation requirements. Accredited for compliance with ISO/IEC 17025.

TESTING LABORATORY REPORT



Reported Nathan Olsen
by:

Checked Robert Irwin
by:

Date : 15-Nov-11
Test No:

AZT0173.11.
xls

250

NATA Accredited Laboratory No: 15147

Wind and Water Penetration Testing

Testing to AS 2047.1 as per test method 4420.0 to .6

Manufacturer / Customer

Test Sample Data

Size

KOMMERLING

1550

Unit type TILT & TURN/FIXED
Unit code GOLD C70

H (mm)

W (mm) 1800

Design Pa: 4000

Tested For	Y/N	Rating	Units
Structural Deflection?	Yes	4000	Pa
Air Infiltration?	Yes	75/150	Pa
Operating Force Initial / constant?		N/A	N
Water Penetration ?	Yes	1000	Pa
		Pos 6600	
Ultimate Strength ?	Yes	Neg 6800	Pa

Deflection Ratio

Test Unit Specifications

Results

	Sizes		Н	w	Area sq m	Glass Type	Structural Framing Member	Span (mm)	Allowable Deflection	Deflection Result	Actual Ratio	Test Press (Pa)	Results
Frame			1550	1800	2.79		Interlock P						
	Fixed Sash		1550	900	1.40		Interlock N						
Sash	Hinged Sas	sh 2	1470	830	1.22		Mullion P	1485	5.94	2.83	525		
							Mullion N	1485	5.94	3.29	525	4000	Р
	Thicknes	s (mm)	Н	W			Transom P						
	Fixed Sash	4/1.52/4	1450	810	1.17	Laminated	Transom N						
Glass	Sash 2	4/1.52/4	1360	720	0.98	Laminated	H/L Trans P						
							H/L Trans N						
							H/L Mullion P						
							H/L Mullion N						
							Meet Style P						
							Meet Style N						
							Spare						
							Spare						

TESTING LABORATORY REPORT

Test equipments

The test equipment and methods used in the above test comply with the requirements of AS 4420.1-6.

Test Specimen

See drawings at the end of this report.

Test Methods

The test unit was fixed into the rig as outlined in AS 4420.1.

Deflection Test

The unit was subjected to both positive and Negative pressure as prescribed in AS 4420.2. After the initial settling in of the unit at the 50% of the required test pressure, the differential pressure was then applied slowly until the nominated design pressure was reached in Positive. This process was then repeated for the Negative.

Results of Test

The test unit satisfied the requirements of AS 2047.1 in both the positive and negative deflection at the nominated design pressure.

<i>,</i>	nc	AM	vat	IAN	

Observations			
NIL			

Air Infiltration Test

The test was first completely sealed against air leakage as per AS 4420.4 to determine the air leakage of the test rig. It was then subjected to 75 Pa of both positive and negative pressure, and 150 Pa of both negative and positive pressure. Differential pressures were recorded. The test unit was then unsealed and subjected to 75 Pa of both positive and negative pressure. Differential pressures were recorded and air leakage then calculated. The actual leakage of the test unit was then determined.

Barometric pressure (Pbar):		1017	7	Air temperature $({}^{\circ}C)$		
		SEALED	UNSE	ALED		
Max Pressure (Pa)	Positive (Pa)	Negative (Pa)	Positive (Pa)	Negative (Pa)		
75	3	8	5	11		
150	9	17	13	23		

Test Pressure	Pressure Direction	Building / Window Type	Allowable leakage flow L/s m ²	Test results			
				ls ⁻¹ m ⁻² Positive	ls ⁻¹ m ⁻² Negative	Pos +	Neg -
75 Pa	+/-	Air conditioned	1.0	0.17	0.16	Passed	Passed
75 Pa	- de	Non air conditioned	5.0	0.17	0.16	Passed	
150 Pa	+/-	Air conditioned	1.6	0.20	0.22	Passed	Passed
150 Pa	***	Non air conditioned	8.0	0.20	0.22	Passed	

TESTING LABORATORY REPORT

D	-14-	- 6	4_	_
Resi	IIIS	OT	TE	SI

The test unit satisfied the requirement of AS 2047. The test unit was tested to AS 4420.4. The net flow readings are as follows:

Observation

NIL		

Operating Force

OPERATING FORCE (N)

		Opening Force	Closing Force
Initiating Movement	Sash 1		
Sustaining Movement	Sash 1		
Initiating Movement	Sash 2		
Sustaining Movement	Sash 2		
Initiating Movement	Sash 3		
Sustaining Movement	Sash 3		

A force gauge was attached to the operating handle of the sash to determine the force required to set the sash in motion and thereafter to maintain motion as per AS 4420.3.

Results of test

The Standard does not require operating force testing for this type of window design.

Observations

Test Not Performed

TESTING LABORATORY REPORT

WATER PENETRATION

Water was applied to the exterior of the test unit with no less than 0.05 ls-1m-2 for a period of five minutes at zero pressure. After five minutes, a nominated pressure was applied for fifteen minutes as per AS 4420.5.

Marimoum	BROCCIINO	(Dal	annlind for	1 5	minutos	(Nominated	BEOCCIIES.	١
Maximum	bressure	(Pa)	applied for	TO	minutes	CNOMIMateu	Diessure	,

1000

Results of test

The test unit satisfied the requirement of AS 2047 in positive pressure at the nominated design pressure.

-						200 00
()	n	ser	7/2	Ŧ1	n	nc
•		3 C I	va		v	

NIL			

ULTIMATE STRENGTH TEST


A pressure nominated on part 1 of this report and determined by AS 2047, table 2.5 was applied to the test unit for a period of 10 seconds as per AS 4420.6.

Max. pressure	reached for 10 seconds	
Positive	Negative	
6600	6800	

Dislodgement of any glass? Dislodgement of a frame or any part of a frame?	No
Dislodgement of a frame or any part of a frame?	110
Distougement of a frame of any part of a frame:	No
Removal of alignment with or without its framing sash from a frame?	
Loss of support of a frame such as when it is unstable in its opening in the building structure?	
Failure of any sash, locking device, fasteners or supporting stay which would allow an opening light to come open?	

Observations

NIL		



Page 60ft